



Global Industry Standard on Tailings Management

GISTM tailings facility disclosure for Bell Bay Aluminium – RMD

5 August 2026

Guidance on interpretation of this GISTM tailings facility disclosure:

The following provides the information required under Requirement 15.1.B of the GISTM.

The information provided in this Global Industry Standard on Tailings Management (GISTM) tailings facility disclosure should be read in conjunction with the information relating to Rio Tinto's approach to tailings management that is available on the Rio Tinto website, and the Group-level tailings management information supporting the GISTM tailings facility disclosures that is included in the Appendix to this document.

Where Rio Tinto considers a Rio Tinto internal process, standard, procedure and/or plan gives rise to a materially similar outcome to a requirement of GISTM, Rio Tinto has adopted the relevant defined term from GISTM for the purpose of reporting under Requirement 15.1.B of GISTM, even though the relevant Rio Tinto process may have a different name or achieve a materially similar outcome by different methods.

The information provided in this disclosure contains forward-looking statements (within the meaning of the US Private Securities Litigation Reform Act of 1995) concerning the financial condition, operations and businesses of Rio Tinto. All statements other than statements of historical fact are, or may be deemed to be, forward-looking statements.

Readers should not place undue reliance on these forward-looking statements, including with regard to future investment decisions. This is because forward-looking statements are statements of future expectations that are based on management's current expectations and assumptions and involve known and unknown risks and uncertainties that could cause actual results, performance of, or events affecting Rio Tinto, or the industry, to differ materially from those expressed or implied in these statements.

Refer to the end of this GISTM tailings facility disclosure for further information on the content of this document and on forward-looking statements.

GISTM conformance status

Tailings facility name: Bell Bay Aluminium – RMD

GISTM consequence classification: High

GISTM conformance status: Partial Conformance

Tailings facility status: Closed

Bell Bay Aluminium – Red Mud Dam (RMD) is managed under the Rio Tinto *Management of Tailings and Water Storage Facilities Standard*, which is focused on ensuring safe operation of all our tailings facilities.

The implementation of the GISTM for Bell Bay Aluminium – RMD tailings facility is partially complete. Further work is required on requirements linked to site characterisation, climate change resilience, appointment of the Engineer of Record, updates to the closure design, water management, demonstration of risks being managed to 'as low as reasonably practicable' (ALARP), confirmation of an integrated monitoring system, and management system documentation updates. Final closure of Bell Bay Aluminium – RMD is likely to be brought forward, following an update to the closure design that was commenced in 2025. The remaining GISTM requirements are expected to be closed out in conjunction with the closure of the tailings facility.

With safety and transparency being core principles for Rio Tinto and the GISTM, we have engaged with George Town Council, state government departments and emergency response groups for George Town and will continue to share relevant information and seek inputs as engagement continues. We have an Emergency Preparedness and Response Plan in place that was developed with involvement from local responders and community stakeholders.

1. Description of the tailings facility

Bell Bay Aluminium is located approximately five kilometres from George Town in Tasmania, Australia and is operated by Rio Tinto Aluminium (Bell Bay) Ltd, part of Rio Tinto Aluminium. Bell Bay Aluminium smelter began operating in 1955, processing alumina to produce aluminium.

Bell Bay Aluminium – Red Mud Dam (RMD) dates from the period when an alumina refinery was operated on site. The refinery processed bauxite to produce alumina, and the refining process generated residue (tailings) in the form of a red mud slurry. The dam ceased being used for storage of tailings in 1974 when the refinery was decommissioned. The surface is partially capped and covered in vegetation.

The operating strategy of Bell Bay Aluminium – RMD is restricted to surface water runoff management and safe release of ponded water during rainfall events. Ponded water is released by a manually operated valve located in the western corner. Water is released to the internal water treatment wetlands, in combination with run-off from the smelter site, and then discharged to the Tamar River at an authorised release point. Controlled release of water is undertaken within the environmental permit release limits. An emergency spillway is located at the northern end of the facility.

Closure planning for Bell Bay Aluminium – RMD is underway to minimise environmental risk from water release and further reduce the already very low likelihood of a tailings facility failure. Closure may be implemented in a staged approach while red mud beneficial re-use opportunities are explored.



2. Consequence classification

Credible failure modes for Bell Bay Aluminium – RMD have been identified, and modelling has been undertaken of downstream flooding resulting from potential dam break scenarios. The dam failure consequence classification was assessed in accordance with the GISTM Consequence Classification Matrix. Incremental losses linked to potential population at risk and potential loss of life, environment, health, social, cultural, infrastructure and economic impacts were considered.

The overall GISTM consequence classification for Bell Bay Aluminium – RMD is 'High', due to the potential impacts to smelter personnel in the event of a tailings facility failure.

3. Risk assessment summary

Rio Tinto assesses risks in a manner consistent with the International Standards Organisation's *Risk Management – Guidelines* (ISO 31000) using the Rio Tinto *Risk Management Standard*. Assessments of risks relevant to Bell Bay Aluminium – RMD are undertaken by a multi-disciplinary team. Risks are evaluated in relation to the potential consequences linked to a range of aspects including but not limited to health and safety, social, human rights, environment, infrastructure and local economics, as well as likelihood with risk mitigations in place. The material risks that have been identified for Bell Bay Aluminium – RMD and their associated control measures are summarised in the table below.

Material risk	Control measure(s)	Status
Embankment failure.	Controls implemented to prevent or manage an embankment failure or external embankment erosion include: • Closure of the Bell Bay Aluminium – RMD is to be bought forward including water management improvements; • Developing plans and procedures for the monitoring and surveillance of Bell Bay Aluminium – RMD; • Training for all levels of personnel involved in the management of the tailings facility; • Monitoring tailings facility performance through instrumentation and observation; and • Independent reviews of design and operations by recognised experts.	These controls are implemented and are monitored through Rio Tinto's internal and external assurance activities.

Material risks for the facility are reviewed on a quarterly basis and all other risks are reviewed annually by a multi-disciplinary team. The risk assessments are updated to reflect the current state of the risks and to ensure the control measures remain relevant and effective.

Further risk assessments are to be completed for the Bell Bay Aluminium – RMD to formally assess that all reasonable steps have been taken to reduce both the likelihood and the consequences of a tailings facility failure to as low as reasonably practicable.

4. Impact assessment summary

An impact assessment has been undertaken for Bell Bay Aluminium – RMD using credible flow failure scenarios. The dam break study has been used to identify downstream areas where people are potentially exposed and vulnerable, and to assess potential social, environmental and economic impacts. The modelling indicates that a failure event at Bell Bay Aluminium – RMD would not directly impact any local population centres.

In alignment with the *United Nations Guiding Principles on Business and Human Rights* and Rio Tinto's *Human Rights Policy*, a human rights risk self-assessment was undertaken to identify and address potential human rights risks from a failure at Bell Bay Aluminium – RMD. This includes consequences linked to people's rights around workplace and community health and safety, Indigenous Peoples rights, land access and use, labour rights, inclusion and diversity, and climate change. The assessment, together with stakeholder mapping, has informed mitigation controls and engagement planning with local community.

Independent advisors were engaged to assess the potential social and economic impacts of a failure scenario for Bell Bay Aluminium – RMD. This included the identification of impacts to people, livelihoods, property, community health and wellbeing, cultural heritage and access to services. This assessment, along with the outcomes of stakeholder engagement, have informed the development of practical short-term and long-term recovery plans which would be activated in the unlikely event that a failure occurs.

Potential environmental impacts from inundation following a tailings facility failure on water quality, sensitive terrestrial and aquatic ecosystems, threatened species, and designated areas of conservation significance have been identified and assessed for Bell Bay Aluminium – RMD.

Outcomes from the impact assessments have been provided to and discussed with relevant stakeholders, who have had input into the development of the Emergency Preparedness and Response Plan for the tailings facility that forms part of the overarching emergency preparedness and response for the site.

5. Description of the tailings facility design

The Bell Bay Aluminium - RMD perimeter embankments are an earth-fill design initially constructed in 1955. The northern embankment and portion of the western embankment were then raised, and the eastern embankment was constructed in 1970.

The maximum embankment height is approximately 6 metres above natural ground level. Approximately 670,000 m³ of tailings is stored in the Bell Bay Aluminium – RMD. Ponded water is released from the facility via a manually operated controlled release valve. An emergency spillway is located to the north of the facility and is understood to be designed for a 1:100-year flood event.

Closure designs are currently being reviewed, and progressive closure of the facility is likely to be conducted sooner than planned, with the prevention of water ponding, as well as full capping and revegetation of the facility remaining priority works.

6. Review findings summary

Annual performance reviews are conducted by an independent engineer to review monitoring and surveillance activities and the condition of the tailings facility. The most recent annual performance review included a visual inspection that indicated that there were no signs of distress or significant erosion observed within the impoundment, embankment, spillway and outlet works. Certain works were recommended to support conformance with the GISTM and the Rio Tinto *Management of Tailings and Water Storage Facilities Standard*. These recommendations are being addressed through the closure planning of the Bell Bay Aluminium – RMD.

The additional material findings and associated control measures from the annual performance review are summarised in the table below.

Material review finding	Mitigation measure(s)	Status
Monitoring and surveillance activities to be reviewed and improved to assess the performance of the Bell Bay Aluminium – RMD.	Bell Bay Aluminium – RMD Operations Maintenance and Surveillance (OMS) Manual is to be reviewed on an annual basis.	The OMS Manual has been reviewed, including a risk based review of monitoring and surveillance activities. The increased monitoring and surveillance activities are to be implemented.

7. Environmental and social monitoring programmes

Monitoring programmes form part of Rio Tinto's Health, Safety, Environment and Communities management system, that acts as the environmental social management system.

To support environmental monitoring works, groundwater bores within and adjacent to Bell Bay Aluminium – RMD are monitored for dissolved fluoride as required under the site's environmental permit.

Decant water from the facility gravity feeds to the wetlands, in combination with runoff from the smelter site, and then discharged to the Tamar estuary at an authorised release point. The combined discharge is monitored for pH, aluminium, fluoride, iron, cyanide, ammonia, and hydrocarbons. During the 2025 reporting period there were no exceedances of regulatory compliance limits attributed to decant water from the Bell Bay Aluminium – RMD.

As an ongoing social monitoring measure, tailings information has been and will continue to be provided and updated at regular community meetings with stakeholders. These meetings aim to facilitate an open and meaningful dialogue for community stakeholders to ask questions and raise concerns. An easily accessible grievance mechanism via the smelter's website is in place to receive and resolve formal complaints.

8. Emergency preparedness and response

An Emergency Preparedness and Response Plan (EPRP) has been prepared for Bell Bay Aluminium – RMD as part of Rio Tinto's Business Resilience and Recovery Programme.

The EPRP is based on credible flow failure scenarios and the assessment of potential consequences to people and the environment, and identifies:

- Equipment and personnel resources required to respond to a tailings facility emergency;
- The chain of command in the event of an actual or potential Bell Bay Aluminium – RMD failure;
- Roles and responsibilities of internal employees, responders and other relevant stakeholders;
- Personnel competencies and training needs for all responders;
- Training exercises that are required to be conducted;
- A graduated Trigger Action Response Plan that defines the actions to take to address signs of imminent failure through to full failure;
- Evacuation decision making, co-ordination, and planning requirements; and
- A recovery plan for Bell Bay Aluminium – RMD including immediate responses and checklist for impact assessments and engagement for tailoring longer term recovery plans. The long-term recovery plan will be modified based on stakeholder engagement and information obtained during the post failure impact assessment.

The EPRP articulates roles and responsibilities in the event of a tailings facility failure as well as procedures that need to be followed to minimise harm to people and the environment. It has been developed in consultation with the George Town Council, Department of Natural Resources and Environment Tasmania, Environmental Protection Authority Tasmania and local emergency response groups including George Town Fire Brigade, State Emergency Services (SES) George Town, as well as Tasmania Police. George Town Council also has a Municipal Emergency Management Plan. Simulations have also been conducted on the EPRP to test response in the event of a dam failure.

Bell Bay Aluminium has shared information with and sought input from employees, many of whom are based in the local community, regarding tailings facility emergency preparedness and response. Engagement allowed for stakeholders to be actively involved in the approach to emergency preparedness and response in relation to a potential tailings facility failure and how this integrates into disaster management planning more broadly.

In an emergency, Bell Bay Aluminium has the responsibility of enacting evacuation orders within the site boundary. The George Town Council has responsibility for activating the Municipal Emergency Management Plan if required.

The EPRP will be reviewed and updated at least every three years, including consultation with relevant stakeholders such as the George Town Council and project-affected people.

9. Independent review timing

The independent engineer for Bell Bay Aluminium – RMD conducted an annual performance review in January 2026, with the next review planned for Q4 2026.

The most recent independent review for Bell Bay Aluminium – RMD was conducted in April 2024. The next review is scheduled for 2027.

10. Financial capacity for closure

Bell Bay Aluminium – RMD is 100% owned by Rio Tinto. Rio Tinto confirms it has adequate financial capacity to cover the estimated costs of planned closure, early closure, reclamation, and post-closure monitoring and maintenance of Bell Bay Aluminium – RMD.

IMPORTANT NOTICEContent of document

This document includes figures, classifications, assessments and other information regarding tailings and Rio Tinto's systems. Some of the information provided relies upon judgment based on internal or external reviews of information. Unless otherwise stated the information in the document is based on data available as at the date of this document, and judgments or assessments in the document may be based on data which predates the date of this document. The information and views may change based on new or different information, circumstances or events and should not be relied upon as a forecast or recommendation.

Forward looking statements

The information presented contains forward-looking statements (within the meaning of the US Private Securities Litigation Reform Act of 1995) concerning the financial condition, operations and businesses of Rio Tinto. All statements other than statements of historical fact are, or may be deemed to be, forward-looking statements.

Forward-looking statements are statements of future expectations that are based on management's current expectations and assumptions and involve known and unknown risks and uncertainties that could cause actual results, performance of, or events affecting Rio Tinto, or the industry, to differ materially from those expressed or implied in these statements. Such forward-looking statements involve subjective judgements and determinations based on available geological, technical, contractual and economic information. These could change because of new information from production or mining activities, or changes in economic factors, including changes in market prices and operating costs, changes in the regulatory policies of host governments, or other events. The statements could also be altered by acquisitions and divestments, new discoveries, and extensions or closure of existing mines, as well as the application of improved recovery and tailings techniques. Published statements could also be subject to correction due to errors in the application of internal assurance or published rules or guidance, and changes in that assurance, rules or guidance. Please also refer to further factors and risks as identified in Rio Tinto's most recent Annual Report and Accounts in Australia and the United Kingdom and the most recent Annual Report on Form 20-F filed with the United States Securities and Exchange Commission ("SEC") or Forms 6-K furnished to, or filed with, the SEC.

As such, readers should not place undue reliance on these forward-looking statements, including with regard to future investment decisions.

Rio Tinto undertakes no obligation to publicly update, or revise, any information in the document, including forward-looking statements, as a result of new information, future events or other information.

Appendix A: Group-level tailings management information supporting the GISTM tailings facility disclosures

5 August 2026

Guidance on interpretation of this Appendix to the GISTM tailings facility disclosures:

The following provides Rio Tinto Group-level information relating to tailings management that supports the GISTM tailings facility disclosures. The processes implemented at individual sites may differ slightly from those described here.

The information provided in this Appendix to the Global Industry Standard on Tailings Management (GISTM) tailings facility disclosures should be read in conjunction with the information relating to Rio Tinto's approach to tailings management that is available on the Rio Tinto website.

Where Rio Tinto considers a Rio Tinto internal process, standard, procedure and/or plan gives rise to a materially similar outcome to a requirement of GISTM, Rio Tinto has adopted the relevant defined term from GISTM for the purpose of reporting under Requirement 15.1.B of GISTM, even though the relevant Rio Tinto process may have a different name or achieve a materially similar outcome by different methods.

The information provided in this disclosure contains forward-looking statements (within the meaning of the US Private Securities Litigation Reform Act of 1995) concerning the financial condition, operations and businesses of Rio Tinto. All statements other than statements of historical fact are, or may be deemed to be, forward-looking statements.

Readers should not place undue reliance on these forward-looking statements, including with regard to future investment decisions. This is because forward-looking statements are statements of future expectations that are based on management's current expectations and assumptions and involve known and unknown risks and uncertainties that could cause actual results, performance of, or events affecting Rio Tinto, or the industry, to differ materially from those expressed or implied in these statements.

Refer to the end of this Appendix to the GISTM tailings facility disclosures for further information on the content of this document and on forward-looking statements.

Appendix A: Group-level tailings management information supporting the GISTM tailings facility disclosures

A.1. Rio Tinto's tailings facilities

Key points:

- *Information for the tailings facilities that Rio Tinto operates are included in our interactive tailings disclosure map on the Rio Tinto website.*
- *New tailings facilities at our operations are in various stages of studies and construction; these will be added to the interactive tailings disclosure map over time.*
- *Rio Tinto also has an interest in tailings facilities at non-managed and non-operated sites.*

Rio Tinto operates a diverse portfolio of tailings facilities at various stages of the tailings facility lifecycle, including tailings contained within engineered earthen embankments and tailings deposited into previously mined open pits. Some tailings facilities consist of embankments constructed in a single phase; others have been raised several times over their active life to increase tailings storage capacity.

For each of our tailings facilities where GISTM implementation is either completed or mostly completed, we have published a tailings facility disclosure statement under Principle 15 of the GISTM that provides information on implementation status. In addition, the tailings information published in response to the request for public disclosure on tailings by the Investor Mining and Tailings Safety Initiative (IMTSI) is available for these facilities.

We periodically update the list of tailings facilities to reflect operational and ownership changes, including changes relating to closure or remediation obligations for legacy assets and reclassification of tailing facilities as these develop over the life of operations.

Rio Tinto also has an interest in other mining operations through joint ventures and other business entities, and through our connection to legacy assets. Sites with tailings facilities in which Rio Tinto has an interest include: Alumar, Blackbird, Escondida, Gladstone Power Station, Mineração Rio do Norte, Olette, Ranger, and Saint Cyr. Refer to the operator or owner for further information on these tailings facilities.

A.2. Consequence classification

Key points:

- *Each tailings facility has been assessed against the five potential loss categories defined in the GISTM and assigned a dam failure consequence classification based on the highest consequence classification across the five categories.*
- *Consequence classifications for Rio Tinto's tailings facilities are a result of assessment by qualified and experienced multi-disciplinary teams following consideration of credible failure modes and impact assessments.*
- *Consequence classifications can change over time.*

Annex 2 of the GISTM includes the Consequence Classification Matrix, as shown below. Using this matrix, potential failures of a tailings facility are assessed against five potential loss categories and assigned a dam failure consequence classification. The overall GISTM consequence classification for a tailings facility is the highest classification across the five categories.

It is important to note that consequence classifications are not ratings of the safety condition of a tailings facility or the likelihood of failure; instead, they rate the potential consequence if the tailings facility were to fail.

Dam Failure Consequence Classification	Incremental Losses				
	Potential Population at Risk	Potential Loss of Life	Environment	Health, Social and Cultural	Infrastructure and Economics
Low	None	None expected	Minimal short-term loss or deterioration of habitat or rare and endangered species.	Minimal effects and disruption of business and livelihoods. No measurable effect on human health. No disruption of heritage, recreation, community or cultural assets.	Low economic losses: area contains limited infrastructure or services. <US\$1M.
Significant	1–10	Unspecified	No significant loss or deterioration of habitat. Potential contamination of livestock/fauna water supply with no health effects. Process water low potential toxicity. Tailings not potentially acid generating and have low neutral leaching potential. Restoration possible within 1 to 5 years.	Significant disruption of business, service or social dislocation. Low likelihood of loss of regional heritage, recreation, community or cultural assets. Low likelihood of health effects.	Losses to recreational facilities, seasonal workplaces, and infrequently used transportation routes. <US\$10M.
High	10–100	Possible (1–10)	Significant loss or deterioration of critical habitat or rare and endangered species. Potential contamination of livestock/fauna water supply with no health effects. Process water moderately toxic. Low potential for acid rock drainage or metal leaching effects of released tailings. Potential area of impact 10 km ² – 20 km ² . Restoration possible but difficult and could take > 5 years.	500–1,000 people affected by disruption of business, services or social dislocation. Disruption of regional heritage, recreation, community or cultural assets. Potential for short term human health effects.	High economic losses affecting infrastructure, public transportation, and commercial facilities, or employment. Moderate relocation/compensation to communities. <US\$100M.
Very High	100–1,000	Likely (10 – 100)	Major loss or deterioration of critical habitat or rare and endangered species. Process water highly toxic. High potential for acid rock drainage or metal leaching effects from released tailings. Potential area of impact > 20 km ² . Restoration or compensation possible but very difficult and requires a long time (5 years to 20 years).	1,000 people affected by disruption of business, services or social dislocation for more than one year. Significant loss of national heritage, community or cultural assets. Potential for significant long-term human health effects.	Very high economic losses affecting important infrastructure or services (e.g., highway, industrial facility, storage facilities, for dangerous substances), or employment. High relocation/compensation to communities. < US\$1B.
Extreme	> 1,000	Many (> 100)	Catastrophic loss of critical habitat or rare and endangered species. Process water highly toxic. Very high potential for acid rock drainage or metal leaching effects from released tailings. Potential area of impact > 20 km ² . Restoration or compensation in kind impossible or requires a very long time (> 20 years).	5,000 people affected by disruption of business, services or social dislocation for years. Significant National heritage or community facilities or cultural assets destroyed. Potential for severe and/or long-term human health effects.	Extreme economic losses affecting critical infrastructure or services (e.g., hospital, major industrial complex, major storage facilities for dangerous substances) or employment. Very high relocation/compensation to communities and very high social readjustment costs. >US\$1B.

Rio Tinto has assigned a GISTM consequence classification to each tailings facility that we operate following assessment of credible failure modes, impact assessments and consideration of downstream conditions. These assessments are conducted by multi-disciplinary teams and use in-house and external expertise. The current GISTM consequence classification for each tailings facility is shown in our interactive tailings disclosure map and in our IMTSI tailings disclosure.

There are other consequence classification schemes in use for tailings facilities, and Rio Tinto has previously published the consequence classifications for our tailings facilities based on the relevant local or international scheme. There may be differences in classification ratings between schemes, depending on the criteria used to assign the classifications.

The consequence classification of a tailings facility can change over time for various reasons, including changes to the operational status of the tailings facility, additional construction that changes the configuration of the tailings facility, the completion of engineering works or implementation of other controls that reduce the potential consequences, or when new information is obtained about the tailings facility, or about the social, environmental and local economic context where the tailings facility is situated.

Consequently, Rio Tinto may, from time to time, amend the consequence classification of a tailings facility. Given the nature of the work required to assess if an amendment to a consequence classification is required, there may be a delay between the change in circumstances that leads to the assessment and amending the consequence classification in our GISTM and IMTSI disclosures and in our interactive tailings disclosure map.

A.3. Risk assessments

Key points:

- *Rio Tinto's Risk Management Standard describes our approach to identifying, assessing, managing and mitigating risk.*
- *Tailings risk assessments consider risk scenarios based on credible failure modes.*
- *Risk assessments are conducted by qualified and experienced multi-disciplinary teams.*
- *Identified risks are managed using a 'three lines of defence' approach.*

All of Rio Tinto's tailings facilities have undergone a detailed risk assessment in alignment with Rio Tinto's *Risk Management Standard* and, where relevant, following our internal guidance on risk analysis for dam safety. Using these processes, potential risk scenarios are listed, risk controls and their effectiveness are assessed, and additional controls are identified. The outcome of these risk assessments is a risk classification using Rio Tinto's internal risk classification scheme which determines the materiality of the risks and the approach to mitigating them.

For tailings facilities, the risk analysis is based on credible failure modes. While credible failure modes are possible ways that a tailings facility could fail, the GISTM notes that *"credible catastrophic failure modes do not exist for all tailings facilities"* and *"the term 'credible failure mode' is not associated with a probability of this event occurring and having credible failure modes is not a reflection of facility safety"*.

Credible failure modes can vary over the lifecycle of a tailings facility as the operating conditions change; the risk assessment process takes into account these changes, and risk assessments can be done at different stages in the life cycle (for example, a risk assessment will occur for the operating phase of the tailings facility and will subsequently be reviewed and updated when the tailings facility moves into the closure phase).

Tailings facility risk assessments are conducted by multi-disciplinary teams to consider the potential causes and impacts of a tailings facility failure including to communities and the environment. Rio Tinto has qualified and experienced personnel who participate in these risk assessments, and we also use the expertise and knowledge of external consultants at various times to contribute to and review the outcomes.

We have a structured approach to managing risks associated with tailings facilities, underpinned by our *Management of Tailings and Water Storage Facilities Standard*. We apply a 'three lines of defence' approach to assurance activities to ensure risks are appropriately managed over the lifecycle of the facility.

A.4. Impact assessment, and human exposure and vulnerability

Key points:

- *Impact assessments have been used to inform and identify potential environmental impacts, and potential human exposure and vulnerability to a tailings facility failure.*
- *Human exposure and vulnerability assessments are used to inform the social impact assessments and other social studies that consider social, environmental and local economic contexts relevant to the tailings facility.*
- *A human rights risk self-assessment is used to identify, assess, manage and mitigate any potential impacts to project-affected people's salient human rights, in alignment with the United Nations Guiding Principles on Business and Human Rights and Rio Tinto's Human Rights Policy.*

Rio Tinto's environment Group Standards outline the minimum performance requirements for the management of water quality, air quality, mineral waste (including tailings), land disturbance and rehabilitation, hazardous materials and non-mineral waste as well as biodiversity and natural resource management. Our Health, Safety, Environment and Communities management system ensures that our environment standards are considered collectively with health, safety, and social performance standards as part of the hazard identification and risk management process to identify and control risks associated with business activities.

Regulations in the jurisdictions where we operate require Rio Tinto to conduct environmental impact assessments (EIAs) or social and environmental impact assessments (SEIAs) as part of any new mine development and, where required, expansions to existing operations. Additionally, risk assessments are required to be undertaken that consider climate change, water management and any hazards associated with physiochemical properties and biogeochemistry of tailings. To understand the potential risks associated with climate change affecting the stability of tailings facilities, assessments have been undertaken in line with Rio Tinto's approach to climate risk and resilience assessment for new, operating and closed tailings facilities.

Environmental baseline information and supporting monitoring information for each tailings facility has been incorporated into the integrated knowledge base. Additional environmental assessments have been undertaken as required to supplement the knowledge base to support tailings management risk mitigation approaches.

The intent of Rio Tinto's *Communities and Social Performance Standard* is to prevent, or otherwise minimise, mitigate and remediate adverse effects of Rio Tinto's operations on people, communities and environments, and strengthen positive outcomes. The Standard sets out minimum mandatory requirements, relating to social and human rights risks and impacts, community engagement and Indigenous Peoples.

To assess potential human exposure, and vulnerability, together with social risks and impacts from a tailings facility failure, assessments have been conducted in alignment with international standards, guidelines and best practice approaches, linked to:

- Social knowledge base, community baselines, socio-economic data and local context considerations;
- Social risks resulting from a potential tailings facility failure being considered through the formal, multidisciplinary risk assessment process using Rio Tinto's risk evaluation framework to quantify the potential consequences to people, health and safety, human rights, license to operate, the environment, business integrity, and legal and regulatory compliance;
- Human exposure and vulnerability assessments conducted for each tailings facility to identify induced and inherent vulnerabilities from a failure scenario identified as part of the dam break study, and how this information is used to support emergency response preparedness;
- Social impact assessments being updated to reflect current social contexts, baselines, stakeholders, and dependencies in response to a tailings facility failure event; and
- In alignment with the United Nations *Guiding Principles on Business and Human Rights* and Rio Tinto's *Human Rights Policy*, a targeted human rights risk self-assessment tool is used to consider and manage salient human rights risks resulting from a tailings facility failure. The tool provides a framework for identifying, assessing, mitigating, managing and monitoring human rights risks in alignment with Rio Tinto's *Risk Management Standard* and *Communities and Social Performance Standard*.

A.5. Tailings facility design

Key points:

- *The design of each tailings facility is unique, based on the type of tailings and the location in which the tailings facility is situated.*
- *Our tailings facilities are designed and reviewed by qualified and experienced consultants.*
- *Designs are undertaken to industry standards and leading practice guidance.*

Tailings storage is a substantial design decision when developing a mine, and there are many factors that need to be considered in selecting the site and construction method to safely contain the tailings. Site conditions such as topography, foundation conditions, rainfall, seismic activity, mineral characteristics and proximity to people and communities dictate appropriate siting of tailings facility locations, technology and storage solutions. As a result, each tailings facility is unique.

Depending on the environment and the chemical characteristics of the tailings, the tailings facility may be lined, using a variety of lining systems which are designed to prevent impacts to surface and groundwater systems. In other cases, lining may not be required and storage behind an engineered earthen embankment or within a mined-out open pit may be sufficient. Back-filling of mined-out pits may have advantages for overall risk reduction and will generally be considered as an option for tailings storage where practicable.

As the tailings slurry is collected in the tailings facility, the water separates from the heavier sand and silt particles and is collected at the surface. The water in the tailings facility may then be recycled back to the process plant for reuse to minimise the impacts to the environment.

In addition to the design requirements specified by the GISTM, our *Management of Tailings and Water Storage Facilities Standard* has specific requirements relating to the design of tailings facilities. The design of our tailings facilities is carried out to industry accepted design standards and design criteria by qualified and experienced personnel employed by engineering consulting companies. The designs are also reviewed by independent tailings facility specialists. For our 'Very High' or 'Extreme' consequence classification tailings facilities, oversight and review of the technical aspects of the design is within the remit of the Independent Tailings Review Board.

A.6. Annual performance reviews and dam safety reviews

Key points:

- *Annual performance reviews are undertaken by the Engineer of Record, and findings are reported back to Rio Tinto.*
- *Dam Safety Reviews comprise of independent reviews conducted in alignment with our Management of Tailings and Water Storage Facilities Standard, together with reviews of our As Low As Reasonably Practicable (ALARP) risk assessments.*
- *ALARP demonstration is an ongoing process for the lifecycle of the tailings facility and is a driver for improvements to the management of our tailings facilities.*

Supporting the performance requirements specified by the GISTM, the Rio Tinto *Management of Tailings and Water Storage Facilities Standard* has specific requirements relating to monitoring and design verification. The key requirements are:

- All personnel conducting monitoring, survey and other design verifications must be suitably trained and familiar with the tailings facility performance objectives;
- Reports must be prepared that outline tailings facility performance at specified intervals;
- The Engineer of Record must inspect the tailings facility at least annually and review the operational documentation to confirm that operation of the tailings facility conforms to the intent of the design; and
- Monitoring reports must be reviewed by the Engineer of Record and must confirm that the tailings facility is operating within the design constraints.

To meet these requirements, an annual performance review is undertaken by the Engineer of Record to assess performance of the operation to design, and a review report is then provided to Rio Tinto.

Rio Tinto addresses the GISTM requirements of a Dam Safety Review by undertaking independent reviews and risk analyses processes to demonstrate that risks have been reduced, including to an As Low As Reasonably Practicable (ALARP) level where required.

Design reviews are conducted at various stages of the design process. The independent design review includes detailed technical review of all aspects of the design with emphasis on the design basis analysis including site and material characterisations, water balance, and stability modelling.

The life-of-facility design is reviewed by an independent tailings facility specialist prior to the implementation of the design. Each detailed stage design, including final closure design, is also reviewed by an independent tailings facility specialist prior to start of construction. The independent specialist evaluates the technical aspects of the design including construction drawings and technical specifications and ensures that the stage designs align with the life-of-facility design.

Independent operational reviews are planned for and completed through the tailings facility lifecycle, including closure and post-closure phases, to identify physical hazards associated with geotechnical, hydrological, hydrogeological and performance aspects of the tailings facility. Reviews are conducted at a frequency of not less than once every two years. Following implementation of the GISTM for a tailings facility, the independent reviewer will make a statement on the safety of the tailings facility, in accordance with the requirements of the GISTM.

ALARP demonstration is undertaken predominantly through a formalised quantitative risk assessment process. ALARP demonstration activities are documented, including actions and timing for completion, and associated commentary is provided on the rationale behind the design decisions. We then subsequently confirm that all actions have been implemented to mitigate risks.

The Engineer of Record reviews the ALARP assessment results, followed by an additional review by the Independent Tailings Review Board or senior independent technical reviewer. The Accountable Executive may then take the decision to confirm that the tailings facility is at ALARP level, or direct further works to be undertaken to demonstrate ALARP.

ALARP demonstration is not a one-off event; it is an iterative process through the tailings facility lifecycle, including closure. The Rio Tinto processes listed above align with the GISTM ALARP requirements to:

- Conduct and update risk assessments with a qualified multi-disciplinary team using best practice methodologies at a minimum every three years and more frequently whenever there is a material change either to the tailings facility or to the social, environmental and local economic context; and
- Conduct a review of ALARP at the time of every Dam Safety Review or at least every five years for an existing tailings facility classified as 'High', 'Very High' or 'Extreme'.

A.7. Environmental and social monitoring

Key points:

- *Effective and integrated management of the tailings facility is governed through our Environmental and Social Management System (ESMS).*
- *The business monitors local communities, in terms of social contexts, impacts, dependencies, public perceptions, trust and acceptance, feedback, complaints and grievances through the collection and analysis of data to inform decision making.*
- *Engagement with local authorities and stakeholders is ongoing, with the intent to continue to raise awareness and maintain a shared state of preparedness in the event of tailings facility failure.*
- *Environmental monitoring activities in support of our tailings facilities is ongoing.*

Rio Tinto's Health, Safety, Environment and Communities (HSEC) management system is reflective of the 'plan, do, check, act' concept that integrates procedures and objectives to manage environmental and social risks and impacts in a structured and meaningful way. The HSEC system meets the requirements of the environmental social management system (ESMS) under GISTM, in that it supports sustainable environmental and social performance, reflects clearly defined and repeatable processes, is dynamic, promotes continuous improvements and is integrated with other management systems, including the tailings management system.

Environmental and social monitoring activities are in place to support the management system. Environmental monitoring programs are established based on environmental impact assessments to determine actual and potential impacts from mining projects, which are compared against predicted or modelled impacts as part of the assessment process.

As part of the environmental impact assessment process, Rio Tinto is also required to undertake monitoring of impacts to the receiving environment to satisfy conditions and commitments outlined in statutory approvals and to conform to the requirements of our environment standards.

Monitoring can include, but is not limited to, assessment of impacts of the tailings facility to local and/or regional groundwater quality, surface water quality and local air quality. In most jurisdictions, reporting of environmental performance is through provision of monitoring results to the local regulators, as well as nominated affected stakeholders, and is required on at least an annual basis for the life of the tailings facility, including the closure and post-closure phases.

Our approach to social monitoring involves the collection and monitoring of data linked to socio-economic contexts of local communities, risk and impact assessments, stakeholder feedback, community perception surveys, complaints and grievances, and requests for information. The information gathered is used to manage social risks and impacts, measure performance against targets, and to inform decision making.

Engagement with local communities is used to increase awareness of each tailings facility and our approach to safe tailings management, to build an integrated knowledge base for each tailings facility and local surroundings, collectively develop plans to monitor performance, and to support a maintained shared state of preparedness in the event of a tailings facility failure. A variety of engagement tools and resources have been developed to support local engagement activities.

With safety and transparency being core principles for Rio Tinto and the GISTM, we are engaging with local communities about the tailings facilities located in the areas where we operate and we will continue to share relevant information, seek input and ensure communities are prepared in the unlikely event of a failure.

Community grievances are managed through a mechanism that outlines processes for obtaining, handling, responding to, and remedying complaints and grievances. Our *Communities and Social Performance Standard* requires that each site has a mechanism that has been designed in consultation with communities

and stakeholders, is publicly available, easily accessible, and allows for an appeal process for resolution of complex complaints or grievances.

To date, there have been a small number of reported complaints and requests for additional information in relation to tailings management from local communities across our global footprint. The complaints have been managed in accordance with our internal standards and procedures and responses provided to stakeholders as appropriate. As engagement continues, local communities will have more opportunity to raise questions, seek clarification, express concerns and request information.

A.8. Emergency preparedness and response

Key points:

- *Rio Tinto has a well-established Business Resilience and Recovery Programme, which applies to all emergency situations including tailings-related events.*
- *Immediate emergency response is provided by our emergency response teams, in collaboration with local emergency response groups as required.*
- *We engage with local communities and agencies on emergency response planning and considerations for longer-term recovery.*

Principles 13 and 14 of the GISTM include the requirement for a site-specific tailings facility Emergency Preparedness and Response Plan which includes specific actions to both prepare for and manage an escalating event, and deliver long-term business, social and environmental recovery following a catastrophic failure.

The Business Resilience and Recovery Programme (BRRP) is Rio Tinto's emergency and crisis management framework, ensuring enterprise-wide preparedness to respond to actual and potential incidents and/or events that may impact local communities, the environment, or our business objectives.

Our sites leverage the BRRP framework to address the GISTM requirements. Each site has an emergency response team that acts as first responders to any emergency on site. These teams are trained in rescue, medical aid and evacuations, and regularly practice emergency response scenarios. The role of the public sector or civil emergency response would be significant in the event of a catastrophic tailings facility failure, with their role likely to extend to the assumption of overall incident command in accordance with legislative requirements. In this situation, the site will comply with the directions of the lead response agency and cooperate with their response efforts.

In alignment with the BRRP and to meet the requirements of the GISTM for an Emergency Preparedness and Response Plan, a Tailings Response Plan has been prepared for each tailings facility as part of the overall emergency preparedness and response planning for local communities. The Tailings Response Plan is based on credible flow failure scenarios and the assessment of potential consequences. The plan includes details on roles and responsibilities, chain of command, training competencies, action responses, evacuation procedures and considerations for recovery.

To prepare for long term recovery in the event of a tailings facility failure, we will engage with public sector agencies and other organisations to consider social and environmental response strategies that may be relevant to reconstruction, restoration and recovery activities, tailored to the failure scenario and local context. In the event of a failure, a long-term recovery plan would then be developed and implemented in partnership with all relevant stakeholders supporting the recovery efforts.

A.9. Frequency of independent reviews

Key points:

- *Independent reviews of tailings facility designs are conducted at key stages of the design phase for each of our tailings facilities.*
- *Independent reviews of tailings facility operation are conducted at a frequency of not less than once every two years.*
- *Rio Tinto has a process for appointing Independent Tailings Review Boards for tailings facilities with 'Very High' and 'Extreme' consequence classifications.*

As detailed in Section A.6, the independent reviews undertaken by Rio Tinto include reviews of tailings facility designs, and reviews of tailings facility operation. Independent design reviews will be conducted as required at multiple stages of the design process as it progresses and typically occur at each project stage through pre-feasibility, feasibility, and other check points of the detailed design phase. Independent operational reviews, where an assessment on the performance of the tailings facility is conducted, are conducted at least every three to five years with the frequency determined by the potential consequence.

In addition to these independent reviews, Rio Tinto undertakes Independent Tailings Review Board reviews for tailings facilities with a GISTM consequence classification of 'Very High' and 'Extreme'. The Independent Tailings Review Board's role is to provide the Accountable Executive and senior management with independent, objective, expert advice in identifying, understanding, and managing the risks and opportunities associated with the relevant tailings facility. The Independent Tailings Review Board procedures require:

- A minimum of three members to constitute the Board;
- Additional members to be appointed depending upon the risks associated with, and the complexity of, the tailings facility; and
- A minimum of two internationally recognised expert board members who are independent and external to the business.

A.10. Financial capacity for closure

Key points:

- *Rio Tinto has processes in place for estimating closure costs.*
- *Closure provisions for close-down, restoration and environmental obligations are included in the financial statements described in Rio Tinto's Annual Report.*
- *Rio Tinto's financial statements are audited by an independent auditor.*

The financial provisions and estimated closure costs for sites are included in Rio Tinto's consolidated financial statements in Rio Tinto's *Annual Report*. A copy of the latest *Annual Report* can be downloaded from Rio Tinto's website.

The financial provisions for close-down and restoration costs include the dismantling and demolition of infrastructure, the removal of residual materials, and the remediation of disturbed areas for mines and refineries and smelters. The provision excludes the impact of future disturbance which is planned to occur during the life of mine, so that it represents only incurred disturbance as at the balance sheet date.

Close-down and restoration costs are a normal consequence of mining or production, and the majority of close-down and restoration expenditure is incurred in the years following closure of the mine, refinery or smelter. Although the ultimate cost to be incurred is uncertain, the Group's businesses estimate their costs using current restoration standards, techniques and expected climate conditions. The costs are estimated on the basis of a closure plan and are reviewed at each reporting period during the life of the operation to reflect known developments. The estimates are also subject to formal review, with appropriate external support, at regular intervals.

We use our judgment and experience to determine the potential scope of closure rehabilitation work required to meet the Group's legal, statutory and constructive obligations, and any other commitments made to stakeholders, and the options and techniques available to meet those obligations and estimate the associated costs and the likely timing of those costs. Further details can be found under the heading 'Provision for closure costs' in the Financial Review section of the *Annual Report*.

The financial statements included in the Annual Report are audited by an independent auditor who provides an opinion that the financial statements give a true and fair view of the state of Rio Tinto's affairs, and that the statements have been properly prepared in accordance with international accounting standards. Evaluation of specific provisions for close-down, restoration and environmental obligations ('closure provisions') at certain sites is a recurring Key Audit Matter (KAM) noted in the independent auditors' report. For further information, refer to the Independent Auditor's Reports section of the *Annual Report*.

IMPORTANT NOTICE**Content of document**

This document includes figures, classifications, assessments and other information regarding tailings and Rio Tinto's systems. Some of the information provided relies upon judgment based on internal or external reviews of information. Unless otherwise stated the information in the document is based on data available as at the date of this document, and judgments or assessments in the document may be based on data which predates the date of this document. The information and views may change based on new or different information, circumstances or events and should not be relied upon as a forecast or recommendation.

Forward looking statements

The information presented contains forward-looking statements (within the meaning of the US Private Securities Litigation Reform Act of 1995) concerning the financial condition, operations and businesses of Rio Tinto. All statements other than statements of historical fact are, or may be deemed to be, forward-looking statements.

Forward-looking statements are statements of future expectations that are based on management's current expectations and assumptions and involve known and unknown risks and uncertainties that could cause actual results, performance of, or events affecting Rio Tinto, or the industry, to differ materially from those expressed or implied in these statements. Such forward-looking statements involve subjective judgements and determinations based on available geological, technical, contractual and economic information. These could change because of new information from production or mining activities, or changes in economic factors, including changes in market prices and operating costs, changes in the regulatory policies of host governments, or other events. The statements could also be altered by acquisitions and divestments, new discoveries, and extensions or closure of existing mines, as well as the application of improved recovery and tailings techniques. Published statements could also be subject to correction due to errors in the application of internal assurance or published rules or guidance, and changes in that assurance, rules or guidance. Please also refer to further factors and risks as identified in Rio Tinto's most recent Annual Report and Accounts in Australia and the United Kingdom and the most recent Annual Report on Form 20-F filed with the United States Securities and Exchange Commission ("SEC") or Forms 6-K furnished to, or filed with, the SEC.

As such, readers should not place undue reliance on these forward-looking statements, including with regard to future investment decisions.

Rio Tinto undertakes no obligation to publicly update, or revise, any information in the document, including forward-looking statements, as a result of new information, future events or other information.